



Blane Hunt
Planning and Construction Coordinator
Operations Center

Phone: (910) 678-2557
Fax: (910) 678-7043
email: blanchunt@ccs.k12.nc.us

EMAIL COVER SHEET

Date: **March 22, 2022**

Attention: **Bidders** FAX# See Below

Company: **See Below**

Regarding: **Asphalt Re-Surfacing for Central Service
Administration Office Building Parking Lot**

Number of pages including this one: 2 Original will follow.

Comments:

Attached you will find the Addendum No. 1 for the above referenced project.

Barnhill Contracting Company: jdaniels@barnhillcontracting.com

Diamond Construction: edawson@diamondconstructors.com

Highland Paving Co., Inc: shelbyht@highlandpaving.com

McDonald Material: mcdonaldf@embarqmail.com

Please give me a call if you have any questions.

Signed: _____

Blane Hunt

Confidential and Privileged: The information contained in this facsimile is privileged and confidential information intended for the sole use of the addressee. If the reader of this facsimile is not the intended recipient or the employee or agent responsible for delivering it to the intended recipient, you are hereby notified that any dissemination, distribution, or copying of this correspondence is strictly prohibited. If you have received this FAX in error, please immediately notify the sender, and return the original message by mail to the sender at the address listed below.

Mailing Address: 810 Gillespie Street, Fayetteville, North Carolina 28306



**Project: Asphalt Re-Surfacing
Central Services Administration
Office Building
Fayetteville, North Carolina**

**Addendum No. 1
Date: March 22, 2022**

**Owner: Cumberland County Schools
801 Gillespie Street
Fayetteville, N.C. 28306**

**Bid Date: March 29, 2021
Bid Time: 9:00 AM**

The following changes, additions and clarifications are made to the General Conditions and Specifications for the above referenced project. **Number of pages 1**

Pre-Bid Conference

1. The Contractor shall remove the nine (9) concrete wheel stops so the existing asphalt can be removed then re-install once the new pavement has been placed.
2. A section of asphalt has been cut out near the center of the building. It appears the existing asphalt is ± 4 " thick (picture attached).
3. The existing storm water inlets in the parking lot are to be protected during demolition and placement of new asphalt.
4. Only the existing yellow curb is to be painted back.
5. In reviewing the section of concrete sidewalk to be removed; a section 6' wide X 13'-6" long shall be removed to avoid cutting the concrete. This area is between two cold joints.
6. The marking layout is attached.

Attachments: 2 pages

END OF ADDENDUM NO. 1

Mailing Address: 810 Gillespie Street, Fayetteville, North Carolina 28306